

)	
**	7'-3-1/2" wide X 7-10" high X 20'-1-1/2" long
**	Empty weight: 2,200 lbs.
**	Forklift tubes 6" X 3"–80" OC
**	Forklift tubes 6" x 3" - 48" OC
**	Integrated receivers for wheels
*	Integrated tubes for D-Rings
*	Composite wall panels
*	Recessed threshold
*	3/4" flooring over 24" on center I beams
*	One piece sealed and riveted aluminum roof
**	Full width roll up door or swing doors optional
**	Stackable 3 high fully loaded
<b>\</b>	Payload capacity @7,500 lbs.
**	Galvanized steel frames

	<u>OPTIONS</u>	<u>PRICING</u>
*	Galvanized Steel Finish	\$5,695
*	Roll Door	Included
**	Wheel Inserts	Included
*	MIBOX Decals	Included
*	14 or our 20 ft. units can be shipped	
	on one flatbed semi	
)—		



## **Roof Structure**

- ➤ 4 Custom formed angles \*7-1/2" X 3" \*10 gauge
- 2 Tie down angles
- ➤ 4 Custom corner roof gussets
- > 7 Roof bows @ 30" centers
- → 4 Forged d-rings
- Pre-punched perimeter alignment holes for wall panels

## Floor Structure

- ➤ 3 Custom formed base rails \* 10 gauge
- ➤ 2 Custom formed C-Channel \* 10 gauge
- > 9 | Beams \* 2-1/4" X 4" X 1/8"
- → 4 lifting tubes \* 6" X 3" X 1/8"
- 4 (wheel) receiver tubes \* 2-1/2" X 2-1/2" X 3/16"
- 2 D- Rings tubes \* 2-1/2" X 2-1/2" X 3/16
- Pre-punched perimeter alignment holes for wall panels

## Wall Section

Custom formed corner posts \*10 gauge
Pre-punched alignment holes to attach to base & wall panels

## Composite Wall Panels

- Panels are composed of two, coil-coated metal skins laminated between a low-density, polyethylene core
- Lightweight. Durable. Flexible













