



SPECIFICATIONS

- 7'-31/2" wide X 7'-10" high X 20'-11/2" long
- Empty weight: 2,200 lbs.
- Forklift tubes 6" x 3" 48" OC
- Forklift tubes 6" x 3" 80" OC
- Integrated receivers for wheels
- Integrated tubes for D-Rings
- Composite wall panels
- · Recessed threshold
- 3/4" flooring over 24" on center I-Beams
- One piece sealed and riveted aluminum roof
- Full width roll up door
- · Stackable 3-high fully loaded
- · Payload capacity: 7,500 lbs.
- Galvanized steel frames

Gal	vanized	Steel	Finish	\$5	,835
Gui				Ψυ	

Roll Door	Included!
Wheel Inserts	Included!
MI-BOX Decals	Included!

20 ft. storage and moving containers will generally fit the contents of an apartment or 4-5 rooms of furniture.

MI-BOX Mobile Storage leads the moving and storage industry in customer satisfaction, equipment and service. Our dealership opportunities are designed to provide everything needed to run and operate your own successful portable storage and moving business.

20 ft.

ROOF STRUCTURE

- 4 Custom formed angles, 7½" X 3", 10 gauge
- 2 Tie-down angles
- 4 Custom corner roof gussets
- 7 Roof bows with 30" centers
- 4 Forged D-Rings
- Pre-punched perimeter alignment holes for wall panels



FLOOR STRUCTURE

- 3 Custom formed base rails, 10 gauge
- 2 Custom formed C-Channels, 10 gauge
- 9 I-Beams, 2¹/₄" X 4" X ¹/₈"
- 4 Lifting tubes, 6" X 3" X ¹/₈"
- 4 (wheel) Receiver tubes, 2¹/₂" X 2¹/₂" X³/₁₆"
- 2 D-Ring tubes,
 2¹/₂" X 2¹/₂" X ³/₁₆"
- Pre-punched perimeter alignment holes for wall panels



WALL SECTION

- Custom formed corner posts,
 10 gauge
- Pre-punched alignment holes to attach to base and wall panels
- Composite Wall Panels
 are composed of two
 coil-coated metal skins
 laminated between a
 low-density, polyethylene core
- · Lightweight, Durable, Flexible



14 of our 20 ft. containers can ship on one flatbed semi!









